

SPECS FOR A PRE-FABRICATED BUILDING

- Size 4'-0" x 6'-0" structure with approximate ceiling height of 6'8"
- All welded galvanized steel construction – 14 ga. exterior; 18 ga. interior
- **6' canopy**
- **Two (2) top hung sliding steel doors with lockset**
 - **Cashier windows in each door**
- Painted steel countertop with storage drawer
- 12 ga. galvanized steel tread plate floor
- UL certified electric system
 - 100 amp circuit breaker panel
 - One (1) 115V duplex outlet
 - Surface mounted fluorescent light with lamps
 - **Four (4) duplex Par flood lights with 75W lamps**
 - #10/3 AWG 10' power cord with twist lock male cord cap for electrical hook-up
- 4KW/240V Fan forced heater with integral thermostat
- RV 120V/13,500 BTU roof mounted cool only air conditioner
- **60 HZ 6KW Diesel Generator mounted on hitch end platform**
 - **6 gal. fuel tank, 6000 watt peak load, 5000 watt continuous**
- **Two (2) 12" convex mirrors**
- Wall, floor and ceiling insulation
- Lift ring
- **Gray tinted tempered safety glass (STD-005 has tinted pull down shades)**
- Screened vent windows
- Roof drain pipe
- Painted enamel finish – single color of choice
- **Dual Axle Heavy Duty Trailer complete with:**
 - Grip strut fold down step
 - Leveling jack
 - Safety rails
 - Ball Coupler
 - Tongue with tongue jack and safety chains
 - Four tires
 - Highway legal lights
- **Two (2) "Magnetic" barrier arm gates with controls**
 - Vendor is not responsible for off-loading, distribution, site work, final electrical connections, site mobilization, field-testing, field measuring, erection, supervision of erection.
 - Delivery is due within 12 weeks of award.